BID TAB

2023 RESURFACING PROJECT NO. 502302

ENGINEER'S ESTIMATE \$4,642,000.00

HAMILTON COUNTY ENGINEER'S OFFICE

BID OPENING: APRRIL 27TH, 2023

REF. NO.	ITEM NO.	DESCRIPTION	UNIT	QUANTITIES	UNIT COST	TOTAL
		ROADWAY				
1	201	CLEARING AND GRUBBING	LS	1		
2	202	ASPHALT CURB REMOVED	LF	2200		
3	202	GUARDRAIL REMOVED, INCLUDING END TREATMENTS	LF	9675		
4	251	PARTIAL DEPTH PAVEMENT REPAIR	SY	2495		
5	254	PAVEMENT PLANING (1.5")	SY	5650		
6	254	PAVEMENT PLANING (2.5")	SY	88555		
7	254	PAVEMENT PLANING (3")	SY	7615		
8	441	ASPH. CONC. INTER., TYPE 1, PG 64-22 (LEVELING) (1")	CY	1330		
9	441	ASPH. CONC. INTER., TYPE 1, PG 64-22 (LEVELING) (1.5")	CY	2035		
10	442	ASPHALT CONCRETE SURFACE, TYPE B, 12.5MM, PG 70-22, 448 (1.5")	CY	4250		
11	606	MGS ANCHOR ASSEMBLY TYPE E	EA	17		
12	606	MGS ANCHOR ASSEMBLY TYPE T	EA	74		
13	606	GUARDRAIL, TYPE MGS, STEEL POSTS	LF	8162.5		
14	606	GUARDRAIL POST, 9 FOOT	EA	282		
15	606	GUARDRAIL, TYPE MGS HALF POST SPACING	LF	881.25		
16	611	SAN MH ADJUSTED TO GRADE (B&M)	EA	38		
17	611	WVC ADJUSTED TO GRADE (B&M)	EA	27		
18	611	MONUMENT BOX ADJUSTED TO GRADE	EA	1		
19	614	MAINTENANCE OF TRAFFIC	LS	1		
20	626	BARRIER REFLECTOR, TYPE 2, BI-DIRECTIONAL	EA	165		
21	644	CENTERLINE (4" DOUBLE, SOLID, YELLOW)	LF	35095		
22	644	STOP LINE, 24" WHITE	LF	111		
23	644	CROSSWALK, PIANO KEY	LF	25		
24	644	EDGE LINE, 4" WHITE	LF	65860		
25	644	CHANNELIZING LINE, 8"	LF	96		
26	644	LANE ARROW	EA	4		
27	897	PAVEMENT PLANING, ASPHALT CONCRETE, CLASS A	SY	4780		
28	GCWW 1125	VALVE BOX RESET	EA	28		
29	SPL	REMOVE RAISED PAVEMENT MARKERS	EA	359		
30	SPL	FULL DEPTH PAVEMENT REPAIR (ASPHALT)	SY	6535		
31	SPL	CONCRETE CURB REPAIR, AS DIRECTED BY ENGINEER	LF	120		
32	SPL	ADDITIONAL DRIVEWAY MODIFICATION	CY	80		
33	SPL	DETECTOR LOOP	EA	2		
34	SPL	RECONSTRUCT EXISITING CATCH BASIN/INLET, COMPLETE	EA	4		
35	SPL	BERM STABILIZATION, SINGLE	LF	881.25		
36	SPL	EXTRUDED CONCRETE CURB, 7.5", TYPE G, AS DIRECTED BY ENGINEER	LF	2110		
37	SPL	ASPHALT REJUVENATOR	SY	101365		
38	SPL	REMOVE AND RESET MAILBOX	EA	7		
		BRIDGE ITEMS				
39	512	WATERPROOFING, TYPE 3	SY	135		
40	517	RAILING (DEEP BEAM RAILING, WITHOUT STEEL TUBULAR BACKUP, WITH HANDRAIL AND STEEL POSTS AND ANCHOR BOLTS). AS DIRECTED BY ENGINEER	LF	87.5		

BID TAB

2023 RESURFACING PROJECT NO. 502302

ENGINEER'S ESTIMATE \$4,642,000.00 BID (

HAMILTON COUNTY ENGINEER'S OFFICE BID OPENING: APRRIL 27TH, 2023

REF. NO.	ITEM NO.	DESCRIPTION	UNIT	QUANTITIES	UNIT COST	TOTAL
41	518	SPECIAL - STEEL DRIP STRIP	LF	80		
42	846	POLYMER MODIFIED ASPHALT EXPANSION JOINT	CF	190		
		DRAINAGE ITEMS				
43	202	HEADWALL REMOVED	EA	8		
44	202	PIPE REMOVED (24" AND UNDER)	LF	280		
45	202	PIPE REMOVED (24" AND OVER)	LF	50		
46	601	ROCK CHANNEL PROTECTION, TYPE C, WITH FILTER	CY	20		
47	602	CONCRETE/MASONRY (HW-1)	CY	19.2		
48	611	15" CONDUIT TYPE B, 707.33, AS DIRECTED BY ENGINEER	LF	120		
49	611	24" CONDUIT TYPE B, 707.33, AS DIRECTED BY ENGINEER	LF	160		
50	611	36" CONDUIT TYPE B, 707.33, AS DIRECTED BY ENGINEER	LF	50		
51	SPL	CONTINGENCY AMOUNT	EA	422000	\$1.00	\$422,000.00

		GRAND TOTAL
CONTRACTOR	DATE	