

BID TAB

SIMPSON AVENUE IMPROVEMENTS
 PROJECT NO. 502115
 ENGINEER'S ESTIMATE \$506,000.00

HAMILTON COUNTY ENGINEER'S OFFICE

BID OPENING: May 11, 2023, 10:00 AM

REF. NO.	ITEM NO.	DESCRIPTION	UNIT	QUANTITIES	UNIT COST	TOTAL
		ROADWAY				
1	202	ASPHALT CURB REMOVED	LF	3300		
2	202	PAVEMENT REMOVED (CONCRETE)	SY	10		
3	202	WALK REMOVED	SF	2460		
4	251	PARTIAL DEPTH PAVEMENT REPAIR	SY	100		
5	254	PAVEMENT PLANING (3")	SY	7650		
6	441	ASPH. CONC. INTER., TYPE 1, PG 64-22, (1.5" LEVELING)	CY	330		
7	442	ASPHALT CONCRETE SURFACE, TYPE B, 12.5MM, PG 70-22, 448 (1.5")	CY	310		
8	452	NON-REINFORCED CONCRETE PAVEMENT (7" PAVEMENT)	SY	10		
9	608	5" CONCRETE WALK	SF	1360		
10	608	CURB RAMP	SF	1510		
11	611	SAN MH ADJUSTED TO GRADE (RING)	EA	1		
12	611	SAN MH ADJUSTED TO GRADE (B&M)	EA	4		
13	611	WVC ADJUSTED TO GRADE (RING)	EA	1		
14	611	WVC ADJUSTED TO GRADE (B&M)	EA	7		
15	614	MAINTENANCE OF TRAFFIC	LS	1		
16	644	CENTERLINE (4" DOUBLE, SOLID, YELLOW)	LF	1760		
17	644	CROSSWALK LINE, PIANO KEY	LF	192		
18	659	SEEDING AND MULCHING	SY	50		
19	GCWW 1125	VALVE BOX RESET	EA	1		
20	SPL	REMOVE RAISED PAVEMENT MARKERS	EA	30		
21	SPL	FULL DEPTH PAVEMENT REPAIR (ASPHALT)	SY	300		
22	SPL	ADDITIONAL DRIVEWAY MODIFICATION	CY	10		
23	SPL	REHABILITATE EXISTING CATCH BASIN/INLET, COMPLETE	EA	1		
24	SPL	RECONSTRUCT EXISTING CATCH BASIN/INLET, COMPLETE	EA	12		
25	SPL	EXTRUDED CONCRETE CURB, 7.5" TYPE G, AS DIRECTED BY ENGINEER	LF	3300		
26	SPL	ASPHALT REJUVENATOR	SY	7250		
27	SPL	CONTINGENCY AMOUNT	EA	46000.00	\$1.00	\$46,000.00

GRAND TOTAL

 CONTRACTOR

 DATE