

BID TAB

MT. ALVERNO & PEDRETTI ROADWAY IMPROVEMENTS
 PROJECT NO. 502114
 ENGINEER'S ESTIMATE \$2,112,000.00

HAMILTON COUNTY ENGINEER'S OFFICE
 BID OPENING: May 11, 2023, 10:00 AM

REF. NO.	ITEM NO.	DESCRIPTION	UNIT	QUANTITIES	UNIT COST	TOTAL
		ROADWAY				
1	202	ASPHALT CURB REMOVED	LF	8260		
2	202	CONCRETE CURB REMOVED	LF	250		
3	202	CURB & GUTTER REMOVED	LF	50		
4	202	PAVEMENT REMOVED (CONCRETE)	SY	70		
5	202	WALK REMOVED	SF	2670		
6	203	EXCAVATION, AS DIRECTED BY THE ENGINEER	CY	50		
7	251	PARTIAL DEPTH PAVEMENT REPAIR	SY	1000		
8	254	PAVEMENT PLANING (2.5") (ASPHALT CONCRETE)	SY	22550		
9	254	PAVEMENT PLANING (2.5") (ASPHALT CONCRETE & CONCRETE)	SY	6600		
10	301	ASPHALT CONCRETE BASE, PG 64-22	CY	50		
11	441	ASPH. CONC. INTER., TYPE I, PG 64-22 (1" LEVELING)	CY	825		
12	442	ASPHALT CONCRETE SURFACE, TYPE B, 12.5MM, PG 70-22, 448, (1.5")	CY	1225		
13	452	NON-REINFORCED CONCRETE PAVEMENT (7" PAVEMENT)	SY	70		
14	608	5" CONCRETE WALK	SF	1700		
15	608	CURB RAMP	SF	1935		
16	611	SAN MH ADJUSTED TO GRADE (RING)	EA	2		
17	611	SAN MH ADJUSTED TO GRADE (B&M)	EA	28		
18	611	WVC ADJUSTED TO GRADE (RING)	EA	1		
19	611	WVC ADJUSTED TO GRADE (B&M)	EA	21		
20	611	SPECIAL - GAS VALVE BOX ADJUSTED TO GRADE	EA	2		
21	614	MAINTENANCE OF TRAFFIC	LS	1		
22	644	CENTERLINE (4" DOUBLE, SOLID, YELLOW)	LF	8150		
23	644	LANE LINE, 4"	LF	400		
24	644	CROSSWALK LINE, 12"	LF	1050		
25	644	CROSSWALK LINE, PIANO KEY	SF	168		
26	644	WORD ON PAVEMENT, 120" "SCHOOL"	EA	1		
27	644	STOP LINE, 24" WHITE	LF	134		
28	644	EDGE LINE, 4" WHITE	LF	13700		
29	644	CHANNELIZING LINE, 8"	LF	55		
30	644	LANE ARROW	EA	2		
31	659	SEEDING AND MULCHING	SY	50		
32	GCWW 1125	VALVE BOX RESET	EA	9		
33	SPL	FULL DEPTH PAVEMENT REPAIR (ASPHALT)	SY	2050		
34	SPL	FULL DEPTH PAVEMENT REPAIR (CONCRETE)	SY	1570		
35	SPL	REMOVE RAISED PAVEMENT MARKERS	EA	150		
36	SPL	CONCRETE CURB REPAIR	LF	870		
37	SPL	ADDITIONAL DRIVEWAY MODIFICATION	CY	250		
38	SPL	REHABILITATE EXISTING CATCH BASIN/INLET, COMPLETE	EA	13		
39	SPL	RECONSTRUCT EXISTING CATCH BASIN/INLET, COMPLETE	EA	25		
40	SPL	EXTRUDED CONCRETE CURB, 7.5" TYPE G, AS DIRECTED BY ENGINEER	LF	8625		
41	SPL	ASPHALT REJUVENATOR	SY	29150		
42	SPL	CONTINGENCY AMOUNT	EA	192000	\$1.00	\$192,000.00

GRAND TOTAL

 CONTRACTOR

 DATE