

BID TAB

CLIFF ROAD LANDSLIDE STABILIZATION
 PROJECT NO. 502105
 ENGINEER'S ESTIMATE: \$759,000.00

HAMILTON COUNTY ENGINEER'S OFFICE

BID OPENING: JUNE 15TH, 2023

NUM.	ITEM NO.	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL
CLIFF ROAD		LANDSLIDE STABILIZATION				
		WALL 1				
1	201	CLEARING AND GRUBBING	LS	1		
2	202	PAVEMENT REMOVED	SY	230		
3	202	GUARDRAIL REMOVED	LF	187.5		
4	202	CATCH BASIN REMOVED	EA	1		
5	203	EXCAVATION	CY	1		
6	203	EMBANKMENT	CY	10		
7	204	SUBGRADE COMPACTION	SY	176		
8	204	EXCAVATION OF SUBGRADE	CY	55		
9	254	PAVEMENT PLANING, ASPHALT CONCRETE	SY	203		
10	302	ASPHALT CONCRETE BASE, PG 64-22, (448)	CY	44		
11	304	AGGREGATE BASE	CY	30		
12	407	TACK COAT	GAL	28		
13	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG 64-22	CY	15		
14	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (448)	CY	15		
15	507	STEEL PILES HP14X73, FURNISHED	LF	690		
16	524	DRILLED SHAFTS, 24" DIAMETER, ABOVE BEDROCK	LF	1020		
17	524	DRILLED SHAFTS, 24" DIAMETER, INTO BEDROCK	LF	570		
18	606	GUARDRAIL, TYPE MGS QUARTER POST SPACING	LF	187.5		
19	614	DETOUR SIGNING	LS	1		
20	644	CENTER LINE	MI	0.03		
21	644	EDGE LINE, 6"	MI	0.05		
22	654	COMMERCIAL FERTILIZER	TON	0.02		
23	659	SEEDING AND MULCHING	SY	78		
24	659	TOPSOIL	CY	9		
25	659	WATER	MGAL	1		
		WALL 2				
26	201	CLEARING AND GRUBBING	LS	1		
27	202	PAVEMENT REMOVED	SY	172		
28	202	GUARDRAIL REMOVED	LF	175		
29	203	EXCAVATION	CY	11		
30	203	EMBANKMENT	CY	3		
31	204	SUBGRADE COMPACTION	SY	160		
32	204	EXCAVATION OF SUBGRADE	CY	54		

BID TAB

CLIFF ROAD LANDSLIDE STABILIZATION
 PROJECT NO. 502105
 ENGINEER'S ESTIMATE: \$759,000.00

HAMILTON COUNTY ENGINEER'S OFFICE
 BID OPENING: JUNE 15TH, 2023

NUM.	ITEM NO.	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL
33	254	PAVEMENT PLANING, ASPHALT CONCRETE	SY	1470		
34	302	ASPHALT CONCRETE BASE, PG 64-22, (448)	CY	40		
35	304	AGGREGATE BASE	CY	27		
36	407	TACK COAT	GAL	26		
37	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG 64-22	CY	14		
38	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (448)	CY	14		
39	507	STEEL PILES HP14X73, FURNISHED	LF	690		
40	524	DRILLED SHAFTS, 24" DIAMETER, ABOVE BEDROCK	LF	1005		
41	524	DRILLED SHAFTS, 24" DIAMETER, INTO BEDROCK	LF	565		
42	606	GUARDRAIL, TYPE MGS HALF POST SPACING	LF	175		
43	614	DETOUR SIGNING	LS	1		
44	644	CENTER LINE	MI	0.03		
45	644	EDGE LINE, 6"	MI	0.05		
46	654	COMMERCIAL FERTILIZER	TON	0.03		
47	659	SEEDING AND MULCHING	SY	168		
48	659	TOPSOIL	CY	19		
49	659	WATER	MGAL	0.5		
INCIDENTALS						
50	623	CONSTRUCTION LAYOUT STAKES AND SURVEYING	LS	1		
51	624	MOBILIZATION	LS	1		
SPECIAL						
52	SPL	CONTINGENCY AMOUNT (10%)	EA	69,000.000	\$1.00	\$69,000.000

 CONTRACTOR

 DATE

GRAND TOTAL