

BID TAB

2024 RESURFACING
 PROJECT NO. 502402
 ENGINEER'S ESTIMATE \$4,686,000.00

HAMILTON COUNTY ENGINEER'S OFFICE

BID OPENING: FEBRUARY 8TH, 2024

REF. NO.	ITEM NO.	DESCRIPTION	UNIT	QUANTITIES	UNIT COST	TOTAL
		ROADWAY				
1	202	ASPHALT CURB REMOVED	LF	17220		
2	202	GUARDRAIL REMOVED, INCLUDING END TREATMENTS	LF	8637.5		
3	203	EXCAVATION	CY	60		
4	204	SUBGRADE COMPACTION	SY	330		
5	251	PARTIAL DEPTH PAVEMENT REPAIR	SY	1000		
6	254	PAVEMENT PLANING (2.5") (ASPHALT CONCRETE)	SY	67675		
7	254	PAVEMENT PLANING (2.5") (CONCRETE)	SY	150		
8	304	AGGREGATE BASE	CY	65		
9	441	ASPH. CONC. INTER., TYPE 1, PG 64-22 (LEVELING) (1")	CY	1805		
10	441	ASPH. CONC. INTER., TYPE 1, PG 64-22 (LEVELING) (1.5")	CY	240		
11	442	ASPHALT CONCRETE SURFACE, TYPE B, 12.5MM, PG 70-22, 448 (1.5")	CY	2905		
12	606	MGS ANCHOR ASSEMBLY TYPE E	EA	11		
13	606	MGS ANCHOR ASSEMBLY TYPE T	EA	37		
14	606	GUARDRAIL, TYPE MGS, STEEL POSTS	LF	8687.5		
15	606	GUARDRAIL POST, 9 FOOT	EA	280		
16	606	GUARDRAIL, TYPE MGS HALF POST SPACING	LF	875		
17	611	ST MH ADJUSTED TO GRADE (B&M)	EA	4		
18	611	SAN MH ADJUSTED TO GRADE (B&M)	EA	23		
19	611	WVC ADJUSTED TO GRADE (B&M)	EA	12		
20	611	MONUMENT BOX ADJUSTED TO GRADE	EA	2		
21	614	MAINTENANCE OF TRAFFIC	LS	1		
22	626	BARRIER REFLECTOR, TYPE 2, BI-DIRECTIONAL	EA	212		
23	644	CENTERLINE (4" DOUBLE, SOLID, YELLOW)	LF	21959		
24	644	STOP LINE, 24" WHITE	LF	72		
25	644	CROSSWALK LINE, 12"	LF	188		
26	644	CROSSWALK, PIANO KEY	LF	372		
27	644	EDGE LINE, 4" WHITE	LF	34488		
28	644	CHANNELIZING LINE, 8"	LF	555		
29	644	LANE ARROW	EA	14		
30	644	TRANSVERSE/DIAGONAL LINE	LF	168		
31	644	WORD ON PAVEMENT, 120" "SCHOOL"	EA	2		
32	897	PAVEMENT PLANING, ASPHALT CONCRETE, CLASS A	SY	2115		
33	GCWW 1125	VALVE BOX RESET	EA	26		
34	SPL	REMOVE RAISED PAVEMENT MARKERS	EA	201		
35	SPL	FULL DEPTH PAVEMENT REPAIR (ASPHALT)	SY	10817		
36	SPL	CONCRETE CURB REPAIR, AS DIRECTED BY ENGINEER	LF	200		
37	SPL	ADDITIONAL DRIVEWAY MODIFICATION	CY	40		
38	SPL	DETECTOR LOOP	EA	7		
39	SPL	REHABILITATE EXISITING CATCH BASIN/INLET, COMPLETE	EA	34		
40	SPL	RECONSTRUCT EXISITING CATCH BASIN/INLET, COMPLETE	EA	26		
41	SPL	BERM STABILIZATION, SINGLE	LF	875		
42	SPL	EXTRUDED CONCRETE CURB, 7.5", TYPE G, AS DIRECTED BY ENGINEER	LF	17170		
43	SPL	ASPHALT REJUVENATOR	SY	68987		
44	SPL	REMOVE AND RESET MAILBOX	EA	23		

BID TAB

2024 RESURFACING
 PROJECT NO. 502402
 ENGINEER'S ESTIMATE \$4,686,000.00

HAMILTON COUNTY ENGINEER'S OFFICE

BID OPENING: FEBRUARY 8TH, 2024

REF. NO.	ITEM NO.	DESCRIPTION	UNIT	QUANTITIES	UNIT COST	TOTAL
		BRIDGE ITEMS				
45	512	WATERPROOFING, TYPE 3	SY	270		
46	517	RAILING (DEEP BEAM RAILING, WITH STEEL TUBULAR BACKUP, AND TYPE 2 STEEL POSTS AND ANCHOR BOLTS), AS DIRECTED BY ENGINEER	LF	62.5		
47	518	SPECIAL - STEEL DRIP STRIP	LF	186		
48	606	GUARDRAIL, TYPE 5	LF	100		
49	606	BRIDGE TERMINAL ASSEMBLY, TYPE 4	EA	4		
50	846	POLYMER MODIFIED ASPHALT EXPANSION JOINT	CF	135		
51	SPL	CONTINGENCY AMOUNT (10%)	EA	426,000.00	\$1.00	\$426,000.00

 CONTRACTOR

 DATE

GRAND TOTAL