

BID TAB

GOSLING ROAD LANDSLIDE CORRECTION
 PROJECT NO. 502309
 ENGINEER'S ESTIMATE: \$495,000.00

HAMILTON COUNTY ENGINEER'S OFFICE

BID OPENING: APRIL 11TH, 2024

NUM.	ITEM NO.	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL
GOSLING ROAD		LANDSLIDE CORRECTION				
1	201	CLEARING AND GRUBBING	LS	1		
2	202	GUARDRAIL REMOVED	LF	212.5		
3	203	EMBANKMENT	CY	100		
4	203	ROADWAY EXCAVATION INCLUDING SAW CUTTING	CY	90		
5	204	SUBGRADE COMPACTION	SY	250		
6	254	PAVEMENT PLANING, ASPHALT CONCRETE (3")	SY	1160		
8	301	ASPHALT CONCRETE BASE, PG 64-22, 448 (9")	CY	65		
7	304	AGGREGATE BASE (6")	CY	45		
9	407	TACK COAT, BITUMINOUS (0.08 GAL/SY)	GAL	230		
10	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, PG 64-22, (1.5")	CY	60		
11	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG 64-22 (1.5")	CY	60		
12	524	PIERS 30" DIAMETER ABOVE ROCK INCL REINFORCING STEEL	LF	565		
13	524	PIERS 30" DIAMETER INTO ROCK INCL REINFORCING STEEL	LF	280		
14	524	PLUG PIERS 30" DIAMETER	LF	1130		
15	606	GUARDRAIL, TYPE MGS, STEEL POSTS	LF	212.5		
16	614	DETOUR SIGNING	LS	1		
17	644	CENTERLINE (4", DOUBLE, YELLOW)	LF	600		
18	644	EDGE LINE, 4" WHITE	LF	1200		
19	659	SEEDING AND MULCHING	SY	60		
20	SPL	RPM REMOVED	EA	12		
		INCIDENTALS				
21	623	CONSTRUCTION LAYOUT STAKES AND SURVEYING	LS	1		
22	624	MOBILIZATION	LS	1		
		SPECIAL				
23	SPL	CONTINGENCY AMOUNT (10%)	EA	45000	\$1.00	\$45,000.00

 CONTRACTOR

 DATE

GRAND TOTAL