

BID TAB

SPRINGDALE ROAD (POOLE TO COLERAIN)
 PROJECT NO. 502314
 ENGINEER'S ESTIMATE \$1,364,000.00

HAMILTON COUNTY ENGINEER'S OFFICE

BID OPENING: APRIL 11TH, 2024

REF. NO.	ITEM NO.	DESCRIPTION	UNIT	QUANTITIES	UNIT COST	TOTAL
ROADWAY ITEMS						
1	202	ASPHALT CURB REMOVED	LF	200		
2	202	GUARDRAIL REMOVED, INCLUDING END TREATMENTS	LF	225		
3	202	PAVEMENT REMOVED (ASPHALT)	SY	70		
4	202	PAVEMENT REMOVED (CONCRETE)	SY	25		
5	202	WALK REMOVED	SF	450		
6	202	CONCRETE CURB REMOVED	LF	115		
7	251	PARTIAL DEPTH PAVEMENT REPAIR	SY	250		
8	254	PAVEMENT PLANING (3")	SY	31150		
9	441	ASPH. CONC. INTER., TYPE 1, PG 64-22 (LEVELING) (1.5")	CY	1300		
10	442	ASPHALT CONCRETE SURFACE, TYPE B, 12.5MM, PG 70-22, 448 (1.5")	CY	1300		
11	452	NON-REINFORCED CONCRETE PAVEMENT (8" DRIVE APRONS)	SY	25		
12	606	GUARDRAIL, TYPE MGS, WITH STEEL POSTS	LF	400		
13	606	MGS ANCHOR ASSEMBLY, TYPE E	EA	1		
14	606	MGS ANCHOR ASSEMBLY, TYPE T	EA	1		
15	608	5" CONCRETE WALK	SF	225		
16	608	CURB RAMP	SF	480		
17	611	ST MH ADJUSTED TO GRADE (B&M)	EA	7		
18	611	SAN MH ADJUSTED TO GRADE (B&M)	EA	1		
19	611	WVC ADJUSTED TO GRADE (B&M)	EA	6		
20	611	SPECIAL - GAS VALVE BOX ADJUSTED TO GRADE	EA	2		
21	614	MAINTENANCE OF TRAFFIC	LS	1		
22	644	CENTERLINE (4" DOUBLE, SOLID, YELLOW)	LF	6830		
23	644	STOP LINE, 24" WHITE	LF	264		
24	644	CROSSWALK LINE, 12"	LF	940		
25	644	CROSSWALK, PIANO KEY	SF	140		
26	644	EDGE LINE, 4" WHITE	LF	7709		
27	644	CHANNELIZING LINE, 8"	LF	2550		
28	644	LANE LINE, 4"	LF	2915		
29	644	LANE ARROW	EA	47		
30	644	TRANSVERSE/DIAGONAL LINE	LF	725		
31	644	WORD ON PAVEMENT, 120" "SCHOOL"	EA	1		
32	809	STOP-LINE RADAR DETECTION	EA	3		
33	GCWW 1125	VALVE BOX RESET	EA	5		
34	SPL	REMOVE RAISED PAVEMENT MARKERS	EA	50		
35	SPL	FULL DEPTH PAVEMENT REPAIR (ASPHALT)	SY	850		
36	SPL	CONCRETE CURB REPAIR, AS DIRECTED BY ENGINEER	LF	30		
37	SPL	REHABILITATE EXISTING CATCH BASIN/INLET, COMPLETE	EA	1		
38	SPL	RECONSTRUCT EXISTING CATCH BASIN/INLET, COMPLETE	EA	2		
39	SPL	EXTRUDED CONCRETE CURB, 7.5", TYPE G, AS DIRECTED BY ENGINEER	LF	315		
40	SPL	ASPHALT REJUVENATOR	SY	31100		
DRAINAGE ITEMS						
41	202	PIPE REMOVED (24" AND UNDER)	LF	80		
42	611	12" CONDUIT TYPE B, 707.33, AS DIRECTED BY ENGINEER	LF	80		
43	SPL	CONTINGENCY AMOUNT	EA	124000	\$1.00	\$124,000.00

CONTRACTOR _____

DATE _____

GRAND TOTAL